

**UF Health Shands Hospital** 

Facilities

## FACILITIES BUILDING STANDARDS

Section 07 0000 Thermal and Moisture Protection

Publish date: 05/16/2017

## Firestopping

- 1. All rated wall penetrations shall be sealed with a UL-listed method and have correct labeling attached, which includes the UL-number, project number, contractor name included. Throughout the scope of the project, the same manufacturer's system (Hilti, 3M, etc) must be provided; systems must not mix.
- 2. All rated walls in renovation areas must be sealed at the conclusion of each work shift, in order to maintain the rated wall assembly.
- 3. In renovation work, contractor must verify and seal <u>all</u> penetrations within the renovation area, even in existing partitions with existing openings.
- 4. Provide EZ-Paths at all rated walls that have more than two penetrations required for wire/cable. All EZ-Paths must be bounded to cable tray.

## Fire and Smoke Assembly Identification

- The following labeling/wording for fire/smoke assemblies shall be provided: SMOKE-TIGHT WALL – PROTECT ALL OPENINGS
  1-HOUR FIRE WALL – PROTECT ALL OPENINGS
  1-HOUR FIRE + SMOKE WALL – PROTECT ALL OPENINGS
  2-HOUR FIRE WALL – PROTECT ALL OPENINGS
  2-HOUR FIRE AND SMOKE WALL – PROTECT ALL OPENINGS
- 2. All fire-rated partitions shall be stenciled on both sides of the partition.

## **Interior and Exterior Joint Sealants**

1. Sealant colors must be white or match adjacent paint color.